

Section VIII. Bill of Quantities

PROGRAM OF WORKS

Name of Project: CONSTRUCTION OF TWO (2) STOREY RHWG BUILDING (PHASE 02 - COMPLETION)		Location: Roma Norte, Enrile, Cagayan			
Total Project Cost:		Project Duration: 120.00		Calendar Days	
Source of Fund:		Mode of Procurement:		Bidding	
Date: 15 May 2024		Source of Manpower:		Straight Contract	
Item No.	Item Description	Quantity	Unit	Unit Cost	Amount
1	GENERAL REQUIREMENTS	1.00	lot		
2	STRUCTURAL & MASONRY WORKS	1.00	l.s.		
3	ARCHITECTURAL WORKS	1.00	l.s.		
4	PLUMBING WORKS	1.00	l.s.		
5	FIRE-SPRINKLER	1.00	l.s.		
6	ELECTRICAL, AUXILLIARY & FIRE PROTECTION	1.00	l.s.		
7	MECHANICAL WORKS	1.00	l.s.		
8	ROOFING WORKS	1.00	lot		
9	MISCELLANEOUS	1.00	lot		
A	Total Direct Cost (Material, Labor and Equipment)				
B	OCM				
C	Contractor's Profit				
D	VAT				
TOTAL PROJECT COST					

GENERAL CONDITION AND REQUIREMENTS

All normal work shall be performed during normal daylight hours.
If work is required overnight, proper lighting must be installed properly illuminating the working area.
Work may be required on weekends/holidays
Equipments shall be checked prior to use and authorized person shall only be allowed to operate the equipment/s.
All dimensions/levels/plumbness etc. indicated in the drawing plans are to be verified on site
The contractor shall control control the generation of dust, flying and falling particles due to the activity
The contractor shall provide warning signages
All rebar works shall be inspected prior to formworks installation/concreting works
All materials/fixtures/color scheme/tiles shall be approved by the end user prior installation/application (Contractor shall submit samples for approval)

BILL OF QUANTITIES

DRN: _____

Name of Project:	CONSTRUCTION OF TWO (2) STOREY RHWG BUILDING (PHASE 02 - COMPLETION)	Location:	Roma Norte, Enrile, Cagayan
Total Project Cost:		Project Duration:	120 Working Days
Source of Fund:		Mode of Procurement:	
Date:	15 May 2024	Source of Marpower:	Straight Contract (Bidding)

Item No.	Item Description	Quantity	Unit	Material Cost	Labor Cost	Unit Cost	Amount
A GENERAL REQUIREMENTS							
1.1	Mobilization/Demobilization	1.00	lot				
1.2	Permits, Clearances & Licenses	1.00	lot				
1.3	Health & Safety, Baricades, Safety Nets, Worker Safety Gears	1.00	lot				
1.4	Testing and Commissioning	1.00	lot				
1.5	Temporary Facility	1.00	lot				
SUB - TOTAL (GENERAL REQUIREMENTS)							
2 STRUCTURAL & MASONRY WORKS							
2A GROUND FLOOR LEVEL							
	Chipping/Demolition Works						
	Chipping/Demolition Works	1.00	lot				
	Perimeter Fence						
	4" CHB	5,945.00	pcs				
	Cement	1,176.00	bags				
	S1 - Aggregates	37.00	cum				
	Pumasañ - Aggregates	32.00	cum				
	3/4" - Aggregates	30.00	cum				
	16mmØ RSB	2,789.93	kg/s				
	10mmØ RSB	3,807.37	kg/s				
	6mmØ RSB	13.20	kg/s				
	Conbar Wire	525.00	lm.				
	Barb Wire	3,150.00	lm.				
	2" G.I. Pipe, Sch40	20.00	pcs				
	2" G.I. Cap, Sch40	80.00	pcs				
	Tiewire	8.00	roll/s				
	Formworks/Falseworks/Scaffoldings	1.00	lot				
	Stairs	3.19	cum				
	Cement	29.00	bags				
	S1 Aggregates	1.59	cum				
	3/4" Aggregates	3.19	cum				
	16mmØ RSB	94.81	kg/s				
	10mmØ RSB	74.07	kg/s				
	Tiewire, #16	1.27	kg/s				
	Formworks/Falseworks/Scaffoldings	1.00	lot				
2B SECOND FLOOR LEVEL							
	Columns	13.89					
	Cement	126.00	bags				
	S1 Aggregates	6.95	cum				
	3/4" Aggregates	13.89	cum				
	20mmØ RSB	2,240.00	pcs				
	10mmØ RSB	1,443.87	pcs				
	Tiewire, #16	27.63	kg/s				
	Formworks/Falseworks/Scaffoldings	151.20	sq.m				
	CHB with Lintel & Stiffener Columns		sq.m				
	4" CHB	4,147.00	pcs				
	6" CHB	2,143.00	pcs				

	Cement	524.00	bg/s			
	10mmØ RSB	1,495.60	kg/s			
	Tie-wire, #16	11.22	kg/s			
	S1 Aggregates	28.90	cum.			
	3/4" Aggregates	3.00	cum.			
	Roof Beams & Conc. Gutter	35.96				
	Cement	321.00	bg/s			
	S1 Aggregates	17.78	cum.			
	3/4" Aggregates	35.96	cum.			
	16mmØ RSB	3,959.41	pc/s			
	12mmØ RSB	662.57	kg/s			
	10mmØ RSB	2,714.94	kg/s			
	Tie-wire, #16	36.98	kg/s			
	Formworks/Falseworks/Scaffoldings	316.47	sq.m.			
SUB - TOTAL (STRUCTURAL & MASONRY WORKS)						
3	ARCHITECTURAL WORKS					
	Plastering (Second Floor)	967.69				
	Plaster sand	24.19	cum.			
	Cement	436.00	bg/s			
	Decorative Stucco Wall Finish	1.00	lot			
	Decorative Concrete Mouldings (Ground to Parapet)	1.00	lot			
	Pebble Washout Finish (Ramp/Stair)	1.00	lot			
	Formworks/Falseworks/Scaffoldings	1.00	lot			
	Water Proofing (Second Floor T & B)					
	Cementitious Water Proofing	1.00	pal/s			
	4" Paint Brush	4.00	pcs			
	Cement	2.00	bg/s			
	Water Proofing (Concrete Gutter)					
	Cementitious Water Proofing	4.00	pal/s			
	4" Paint Brush	6.00	pcs			
	Cement	2.00	bg/s			
	Doors (Second Floor)					
	D3 - Solid Wood Panel, Single Swing Door w/ Heavy Duty Lever Type Lockset with Deadbolt and Door Closer, 2.1m x 0.90m	8.00	sets			
	D4 - Solid Wood Panel, Single Swing Door w/ Louver w/ Heavy Duty Lever Type Lockset and Door Closer, 2.1m x 0.90m	4.00	sets			
	D6 - Solid Wood Panel, Single Swing Door w/ Louver w/ Heavy Duty Lever Type Lockset and Door Closer, 2.1m x 0.80m	14.00	sets			
	Windows (Second Floor)					
	W1 (See/Refer to Plan - Window Schedule)	9.00	unit/s			
	W2 (See/Refer to Plan - Window Schedule)	1.00	unit/s			
	W3 (See/Refer to Plan - Window Schedule)	1.00	unit/s			
	W4 (See/Refer to Plan - Window Schedule)	1.00	unit/s			
	W5 (See/Refer to Plan - Window Schedule)	1.00	unit/s			
	W7 (See/Refer to Plan - Window Schedule)	6.00	unit/s			
	W8 (See/Refer to Plan - Window Schedule)	2.00	unit/s			
	W9 (See/Refer to Plan - Window Schedule)	9.00	unit/s			
	W10 (See/Refer to Plan - Window Schedule)	1.00	unit/s			
	Windows Mosquito Screen (Second Floor)					
	Sliding Window Mosquito Screen (Second Floor)	45.26	sq.m.			
	Windows Blinds (Second Floor)					
	Windows Blinds (Second Floor)	61.10	sq.m.			
	Painting (Fence)					
	Concrete Neutralizer	6.00	gal/s			
	Flat Paint (Primer) - Solvent Based, Water Resistant/Water Proof	15.00	pal/s			
	Solvent Semi-gloss (Topcoat) - Solvent Based Water Resistant/Water Proof (Premix)	20.00	pal/s			
	Wall Putty	15.00	pal/s			
	Thinning Solvent	2.00	gal/s			
	7" Paint Roller w/ Pan	20.00	pcs			
	Paint Brush, Assorted	15.00	pcs			
	Epoxy Primer w/ Catalyst, White	10.00	gal/s			
	Painting (Second Floor)					
	Flat, Latex Paint	11.00	pal/s			
	Semi-gloss, Latex Paint	5.00	pal/s			

	Flat, Solvent Based Paint	2.00	pc/s				
	Semi-gloss, Solvent Based Paint	2.00	pc/s				
	Epoxy Primer, White	4.00	gal/s				
	Reflectorized Traffic Paint	4.00	gal/s				
	Wall Putty	4.00	pc/s				
	Body Filler	8.00	gal/s				
	Boral Powder	50.00	kg/s				
	Reducer	4.00	gal/s				
	Tinting Color - Acrylic, Assorted	10.00	lit/s				
	Tinting Color - Solvent Based, Assorted	10.00	lit/s				
	7" Roller Paint	15.00	pc/s				
	4" Baby Roller	10.00	pc/s				
	Paint Brush, Assorted	10.00	pc/s				
	Sanding Paper, Assorted	50.00	pc/s				
	Floor Finish (Second Floor & Stair @ G/F Exterior)						
	60cm x 60cm Homogenous Granite Tile	847.00	pc/s				
	30cm x 30cm Ceramic Floor Tile, Non-skid	224.00	pc/s				
	40cm x 40cm Ceramic Floor Tile, Non-skid	59.00	pc/s				
	30cm x 60cm Ceramic Wall Tile	840.00	pc/s				
	30cm x 60cm Non-skid Homogenous Granite Tile w/ Thread Nosing	94.00	pc/s				
	Tile Adhesive	178.00	bg/s				
	Tile Grout, 2kgs/bg	10.00	bg/s				
	Stainless Steel Tile Trim, Bit	5.00	pc/s				
	4" Diamond Disc, Super Thin	2.00	pc/s				
	Ceiling Finish (Ground Floor)						
	1/4" Gypsum Board	142.00	pc/s				
	Carrying Channel, 5m	117.00	pc/s				
	Double Furring, 5m	175.00	pc/s				
	Wall Angle, G.I.	256.00	pc/s				
	W-Clip	290.00	pc/s				
	1/8" Blind Rivet	10.00	bx/s				
	1/8" Masonry Drill Bit	60.00	pc/s				
	1/8" Steel Drill Bit	30.00	pc/s				
	1 1/2" Black Screw	7,200.00	pc/s				
	Ceiling Finish (Second Floor)						
	1/4" Gypsum Board	126.00	pc/s				
	Carrying Channel, 5m	102.90	pc/s				
	Double Furring, 5m	103.00	pc/s				
	Wall Angle, G.I.	221.00	pc/s				
	W-Clip	250.00	pc/s				
	1/8" Blind Rivet	10.00	bx/s				
	1/8" Masonry Drill Bit	30.00	pc/s				
	1/8" Steel Drill Bit	30.00	pc/s				
	1 1/2" Black Screw	6,300.00	pc/s				
	WPC Ceiling Panel						
	WPC Ceiling Panel	110.00	sq.m				
	Stair and Ramp Railings, Grab Bars (Staircase)						
	Stair and Ramp Railings, Grab Bars (Staircase), Stainless Steel	1.00	lot				
	Wall Cladding						
	WPC Fluted Exterior Panel	5.00	sq.m				
	Stone Cladding	6.05	sq.m				
	SUB - TOTAL (ARCHITECTURAL WORKS)						
4	PLUMBING WORKS						
	SANITARY LINE						
	Second Floor Level						
	Water Closet (One-piece) W/ Complete Accessories	9.00	set/s				
	Lavatory w/ Complete Accessories	7.00	set/s				
	Rainfall Type Shower, Stainless Steel - Heavy Duty	9.00	set/s				
	Faucet, Stainless Steel - Heavy Duty	9.00	set/s				
	Stainless Steel Bidet - Heavy Duty	9.00	set/s				
	Two-way Angle Valve, Stainless Steel	9.00	set/s				
	Sewer Line						
	Pipes (Series 1000)	1.00	lot				

	Fittings and Accessories	1.00	lot				
	WATER LINE (Second Floor)						
	Pipes (PPR)	1.00	lot				
	Fittings and Accessories (PPR)	1.00	lot				
	Clamps/Hanger						
	Clamps/Hanger	1.00	lot				
SUB - TOTAL (PLUMBING WORKS)							
5	FIRE SPRINKLER						
5.1A	Piping System (Ground Floor)						
	B.I. Pipe 25mmØ x 6m (Schedule 40)	12.00	pc/s				
	B.I. Pipe 32mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 40mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 50mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 65mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 75mmØ x 6m (Schedule 40)	5.00	pc/s				
	B.I. Pipe 100mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Fittings	1.00	lot				
	Bracket, Loop hangers, truss block, away braces and supports	1.00	lot				
5.2A	Sprinkler Heads (Ground Floor)						
	Automatic Fire Sprinkler, Std Response	26.00	pc/s				
5.3A	Fire Hose Cabinet (Ground Floor)						
	Fire Hose Cabinet w/ Complete Accessories, 50ft	2.00	set/s				
5.4A	Fire Department Connection (Ground Floor)						
	2-WAY FDC 65x65x100	1.00	set/s				
	Swing Check Valve 100mmØ	1.00	set/s				
5.5A	Room Control Valve (Ground Floor)						
	OS & Y Gate Valve 100mmØ	1.00	set/s				
	Supervisory Switch 100mmØ	1.00	set/s				
	Water Flow Switch 100mmØ	1.00	set/s				
	Pressure Gauge	1.00	set/s				
	Sight Glass 25mmØ	1.00	set/s				
	Ball Valve 25mmØ	1.00	set/s				
	Ball Valve 32mmØ	1.00	set/s				
	Fire Hose Valve 65mm with Cap and Chain	1.00	set/s				
5.1B	Piping System (Second Floor)						
	B.I. Pipe 25mmØ x 6m (Schedule 40)	10.00	pc/s				
	B.I. Pipe 32mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 40mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 50mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 65mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Pipe 75mmØ x 6m (Schedule 40)	5.00	pc/s				
	B.I. Pipe 100mmØ x 6m (Schedule 40)	1.00	pc/s				
	B.I. Fittings	1.00	lot				
	Bracket, Loop hangers, truss block, away braces and supports	1.00	lot				
5.2B	Sprinkler Heads (Second Floor)						
	Automatic Fire Sprinkler, Std Response	24.00	pc/s				
5.3B	Fire Hose Cabinet (Second Floor)						
	Fire Hose Cabinet w/ Complete Accessories, 50ft	1.00	set/s				
5.4B	Room Control Valve (Second Floor)						
	OS & Y Gate Valve 100mmØ	1.00	set/s				
	Supervisory Switch 100mmØ	1.00	set/s				
	Water Flow Switch 100mmØ	1.00	set/s				
	Pressure Gauge	1.00	set/s				
	Sight Glass 25mmØ	1.00	set/s				
	Ball Valve 25mmØ	1.00	set/s				
	Ball Valve 32mmØ	1.00	set/s				
	Fire Hose Valve 65mm with Cap and Chain	1.00	set/s				
SUB - TOTAL (FIRE-SPRINKLER)							
6	ELECTRICAL, AUXILIARY & FIRE PROTECTION						
	Electrical Works						
	Lighting and Power System (Second Floor)						
	Chipping Works	1.00	lot				

	Conduits & Fittings				
	Conduits & Fittings	1.00	lot		
	Wires & Cables				
	a. 2.0mm ² THHN	2.00	bx/s		
	b. 3.5mm ² THHN	3.00	bx/s		
	c. 5.5mm ² THHN	2.00	bx/s		
	Boxes				
	a. Junction Box DT G-16 w/ cover	47.00	pc/s		
	b. Utility Box DT G-16	44.00	pc/s		
	c. Miscellaneous	1.00	lot		
	Wiring Devices				
	a. 1p switch	18.00	pc/s		
	b. 3 way switch	2.00	pc/s		
	d. 1g plate cover	6.00	pc/s		
	e. 2g plate cover	5.00	pc/s		
	f. 3g plate cover	5.00	pc/s		
	g. 1 Gang Outlet, Universal	15.00	pc/s		
	h. 2 Gang Outlet, Universal	24.00	pc/s		
	Lighting Fixtures				
	a. 6" x 6" LED Pinlight, 18W	51.00	pc/s		
	b. Emergency light	15.00	set/s		
	Miscellaneous				
	a. G.I. Tie wire G-16	15.00	kg/s		
	b. Electrical tape	2.00	pc/s		
	c. Rubber tape	2.00	pc/s		
	d. Hanger/support	1.00	lot		
	Fire Alarm System (Ground Floor)				
	ROUGH-INS (BOXES, CONDUITS, WRES & ACCESSORIES)				
	Junction Box 4x4 Ga. #16 w/cover	19.00	pc/s		
	Utility Box 2x4 Ga.#16	2.00	pc/s		
	Pull box 200x200 w/Terminal Block	2.00	pc/s		
	Electrical EMT Pipe 25mma, Connector, Adaptor	1.00	lot		
	1.25mm ² TF Wire (150mts/box)	2.00	bx/s		
	Electrical Tape	2.00	pc/s		
	UNITS, DEVICES & PANEL (Ground Floor)				
	Photo Electric Smoke/Heat Detector, Conventional (ULFM List)	18.00	unit/s		
	Manual Call Station Push Button (ULFM List)	2.00	unit/s		
	Fire Alarm Bell (ULFM List)	2.00	unit/s		
	Fire Alarm Control Panel 6 Zone (ULFM List)	1.00	unit/s		
	Connector, Terminal Block & Fitting	1.00	lot		
	Fire Alarm System (Second Floor)				
	ROUGH-INS (BOXES, CONDUITS, WRES & ACCESSORIES) Ground Floor				
	Junction Box 4x4 Ga. #16 w/cover	17.00	pc/s		
	Utility Box 2x4 Ga.#16	2.00	pc/s		
	Pull box 200x200 w/Terminal Block	2.00	pc/s		
	Electrical EMT Pipe 25mma, Connector, Adaptor	1.00	lot		
	1.25mm ² TF Wire (150mts/box)	2.00	bx/s		
	Electrical Tape	2.00	pc/s		
	UNITS, DEVICES & PANEL (Second Floor)				
	Photo Electric Smoke Detector Conventional (ULFM List)	15.00	unit/s		
	Manual Call Station Push Button (ULFM List)	1.00	unit/s		
	Fire Alarm Bell (ULFM List)	1.00	unit/s		
	Fire Alarm Control Panel 6 Zone (ULFM List)	1.00	unit/s		
	Connector, Terminal Block & Fitting	1.00	lot		
	BGA, Public Address System (Ground Floor)				
	Junction Box 4" x 4" Ga. #16	11.00	pc/s		
	Pull Box 200x200 Ga. #16	2.00	pc/s		
	Electrical PVC Pipe, Adaptor W/ Nut	1.00	lot		
	Speaker Wire 2/16C	2.00	bx/s		
	20watts Speaker Ceiling Mounted	11.00	pc/s		
	Public Address Amplifier	2.00	unit/s		
	Microphone w/ Chime	2.00	set/s		
	Wall Mounted Speaker	4.00	set/s		
	BGA, Public Address System (Second Floor)				

	Junction Box 4" x 4" Ga. #16	10.00	pcs				
	Pull Box 200x200 Ga. #16	2.00	pcs				
	Electrical PVC Pipe, Adaptor W/ Nut	1.00	lot				
	Speaker Wire 2/16C	2.00	bx/s				
	20watts Spesker Ceiling Mounted	10.00	pcs				
	Public Address Amplier	1.00	units				
	Microphona w/ Chime	1.00	sets				
	PANEL BOARDS						
	Panel Boards (Main and Branches)	1.00	sets				
	CCTV (Ground Floor) w/ LCD Monitor - 46" and Recorder, High Resolution, High Definition						
	CCTV, 1080p (Ground Floor) - 5 units	1.00	lot				
	CCTV (Second Floor Floor) w/ LCD Monitor - 45" and Recorder, High Resolution, High Definition						
	CCTV, 1080p (Second Floor Floor) - 6 units	1.00	lot				
	FIRE EXTINGUISHER						
	Fire Extinguisher w/ Cabinet, 10lbs	14.00	sets				
	Solar Street Lights Outdoor - 1000W Solar Parking Lot Lights, 7000K LED Solar Lights, Dusk to Dawn, Motion Sensor, IP65 Waterproof, Commercial Grade	23.00	units				
SUB - TOTAL (ELECTRICAL, AUXILIARY & FIRE PROTECTION)							
7	MECHANICAL WORKS						
	Ventilation (Ground Floor)						
	Exhaust Fan Cassette Type 20 LPS, Heavy Duty	6.00	sets				
	Exhaust Fan Cassette Type 50 LPS, Heavy Duty	2.00	sets				
	4" Flexible Exhaust Duct	6.00	rolls				
	4" Ø Stainless Steel Exhaust Hood	10.00	sets				
	Ventilation (Second Floor)						
	Exhaust Fan Cassette Type 20 LPS, Heavy Duty	12.00	sets				
	4" Flexible Exhaust Duct	9.00	rolls				
	4" Ø Stainless Steel Exhaust Hood	12.00	sets				
	Air-conditioning (Ground Floor)						
	2.5HP Split-type Aircon, Dual Inverter	6.00	sets				
	5Ton Floor Mounted Aircon, Dual Inverter	1.00	sets				
	1.5HP Split-type Aircon, Dual Inverter	1.00	sets				
	Air conditioning (Second Floor)						
	2.5HP Split-type Aircon, Dual Inverter	7.00	sets				
	1.5HP Split-type Aircon, Dual Inverter	1.00	sets				
SUB - TOTAL (MECHANICAL WORKS)							
8	ROOFING WORKS						
	Tinsentry						
	0.6mm Thk, Pre-painted Double/Twin Rib Type Roofing	550.00	sq.m				
	0.6mm Thk, Pre-painted Ridge Roll	30.00	pcs				
	0.6mm Thk, Pre-painted Valley Cutter	6.00	pcs				
	10mm Thk, Insulation Foam - 2S, 50m	11.00	rolls				
	Chicken Wire - G.I. (1" Hole), 90ft	11.00	rolls				
	2" Texscrew	5.00	bx/s				
	Steel Trusses						
	2" x 2" x 4mm Thk, Angular Bar	61.00	pcs				
	2 1/2" x 2 1/2" x 6mm Thk, Angular Bar	53.00	pcs				
	4mm Thk Metal Steel Plate	1.00	pcs				
	2" x 4" C-Purlins, 2.0mm	156.00	pcs				
	12mmØ Plain Bar	15.00	pcs				
	16mmØ Plain Bar	15.00	pcs				
	16mmØ Turn-buckle	12.00	pcs				
	10mm Thk, Metal Steel Plate	1.00	pcs				
	20mmØ Anchor Bolt	204.00	pcs				
	Epoxy Primer w/ Catalyst, Gray	15.00	gal/s				
	Lacquer Thinner	2.00	gal/s				
	2" Paint Brush, Good Quality	5.00	pcs				
	4" Baby Roller, Good Quality	5.00	pcs				
	Welding Rod	5.00	bx/s				
SUB - TOTAL (ROOFING WORKS)							
9	MISCELLANEOUS						

9.1	Acrylic Bull-up Letters W/ LED Backlight (Regional Haven for Women and Girls)	1.00	lot			
9.2	Luminous Emergency Signages, Evacuation/Emergency Plan (Per Room & Hallway- Ground & Second) and Safety Warning Signages (Entrance, Exits, Directional, TPASS, CR Signages, First Aid Kits, Room Assignments/Designation, Fire Alarm), Acrylic - Base	1.00	lot			
9.3	Rehabilitation Works	1.00	lot			
9.4	Fabrication of Gates					
	2.0mm Thk, Stainless Steel Sheet	7.00	pc/s			
	1" x 2" Tubular Stainless Steel, 304 - 2.0mm	5.00	pc/s			
	1" x 1" Tubular Stainless Steel, 304 - 2.0mm	5.00	pc/s			
	3/4" Stainless Steel Pipe, 304 - 2.0mm	1.00	pc/s			
	1" Ø Stainless Steel Pipe, 304, 2.0mm	1.00	pc/s			
	Pillow Block, Heavy Duty	10.00	pc/s			
	4" Stainless Steel Ring, 304	39.00	pc/s			
	1" Ø Continuous Design Stainless Steel Pipe	4.00	pc/s			
	Acrylic Signage -12mm Thk, DSWD Logo	2.00	set/s			
	Consumables	1.00	lot			
9.5	Fire Exit Ladder (Drop-Down Ladder)	1.00	set/s			
SUB - TOTAL (MSCELLANEOUS)						

A	Total Direct Cost (Material, Labor and Equipment)	
B	OCM (12% of A)	
C	Contractor's Profit (8% of A)	
D	VAT (5% of A+B+C)	
TOTAL PROJECT COST		

Name of Bidder: _____

Name of Authorized Representative: _____

Signature of Authorized Representative: _____

Date: _____

Checklist of Technical and Financial Documents

I. TECHNICAL COMPONENT ENVELOPE

Class "A" Documents

Legal Documents

- (a) Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages) in accordance with Section 8.5.2 of the IRR;

Technical Documents

- (b) Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid; **and**
- (c) Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, except under conditions provided under the rules; **and**
- (d) Special PCAB License in case of Joint Ventures; **and** registration for the type and cost of the contract to be bid; **and**
- (e) Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission;
- or**
- (f) Original copy of Notarized Bid Securing Declaration; **and**
- (f) Project Requirements, which shall include the following:
- a. Organizational chart for the contract to be bid;
- b. List of contractor's key personnel (e.g., Project Manager, Project Engineers, Materials Engineers, and Foremen), to be assigned to the contract to be bid, with their complete qualification and experience data;
- c. List of contractor's major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership or certification of availability of equipment from the equipment lessor/vendor for the duration of the project, as the case may be; **and**
- (g) Original duly signed Omnibus Sworn Statement (OSS); **And** if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder.

Financial Documents

- (h) The prospective bidder's computation of Net Financial Contracting Capacity (NFCC).

Class "B" Documents

- (i) If applicable, duly signed joint venture agreement (JVA) in accordance with RA No. 4566 and its IRR in case the joint venture is already in existence;

or

Duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

II. FINANCIAL COMPONENT ENVELOPE

- (j) Original of duly signed and accomplished Financial Bid Form; **and**

Other documentary requirements under RA No. 9184

- (k) Original of duly signed Bid Prices in the Bill of Quantities; **and**
- (l) Duly accomplished Detailed Estimates Form, including a summary sheet indicating the unit prices of construction materials, labor rates, and equipment rentals used in coming up with the Bid; **and**
- (m) Cash Flow by Quarter.

